

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,280-00-00

LEASE NAME Taylor "D"

WELL NUMBER 1

330 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 36 TWP. 10 RGE. 12 (X) or (W)

COUNTY Osborne

Date Well Completed 10-14-93

Plugging Commenced 10-14-93

Plugging Completed 10-14-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-93 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,886'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	230'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Fill hole w/heavy mud. Spot 25 sax cement @3,864' thru drill pipe. Push bridge plug to 715', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 535', spot 100 sax on plug thru drill pipe. Push bridge plug to 280', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax down mouse hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160 5184 KCC

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1993

Ruth Phillips
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1993
10-27-93
CONSERVATION DIVISION
Wichita, Kansas
Form CP-4
Revised 05-88