

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: DOWNING NELSON OIL COMPANY, INC. Address: PO BOX 372 HAYS, KS 67601 Phone: (785) 621-2610 Operator License #: 30717 Type of Well: D & A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 09/26/06 by: Herb Deines (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) NONE Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15 - 195-22,393-00-00 Lease Name: Loflin Family Trust Well Number: 1-22 Spot Location (QQQQ): - C - NE 1390 Feet from [X] North / [ ] South Section Line 1280 Feet from [X] East / [ ] West Section Line Sec. 22 Twp. 13 S. R. 22 [ ] East [X] West County: TREGO Date Well Completed: 09/27/06 Plugging Commenced: 9:15AM 09/27/06 Plugging Completed: 11:15AM 09/27/06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Surface, 222, 8 5/8, 222.75, NONE.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st plug @ 1750' W/25sks 15sks in rat hole Circulated 1st plug 15 minutes W/52Vis Mud
2nd Plug @ 825' W/ 100sks 10sks in mouse hole Plugs displaced with mud
3rd Plug @ 275'W/ 40sks Total 200sks 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing
4th Plug @ 40' W/10sks Completed @ 11:15AM 09/27/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548 Address: PO BOX 763 HAYS, KS 67601

Name of Party Responsible for Plugging Fees: Downing Nelson Oil Co., Inc. State of KS County, Ellis, ss.

Alan Downing (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature] (Address) P.O. Box 372 Hays, KS 67601



and SWORN TO before me this 12 day of October, 2006 My Commission Expires: 7/28/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED OCT 16 2006 KCC WICHITA