

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: DOWNING NELSON OIL COMPANY, INC.  
Address: PO BOX 372 HAYS, KS 67601  
Phone: (785) 621-2610 Operator License #: 30717  
Type of Well: D & A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 09/08/06 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
NONE Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 195-22,386-00-00  
Lease Name: JANICE #1-12 Per RBDms + cpzls PICT 10/20/06 KCC  
Well Number: 1-12  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - SE  
2114 Feet from  North /  South Section Line  
2284 Feet from  East /  West Section Line  
Sec. 12S Twp. 13 S. R. 22  East  West  
County: TREGO  
Date Well Completed: 09/10/06  
Plugging Commenced: 12:15AM 09/10/06  
Plugging Completed: 3:45AM 09/10/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	222	8 5/8	222.61	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st plug @ 4070' W/25sks 5th Plug @ 40' W/10sks 15sks in rat hole Circulated 1st plug 15 minutes W/55Vis Mud  
2nd Plug @ 1725' W/ 25sks 10sks in mouse hole Plugs displaced with mud  
3rd Plug @ 825' W/ 100sks Total 225sks 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing  
4th Plug @ 275' W/40sks Completed @ 3:45AM 09/10/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548  
Address: PO BOX 763 HAYS, KS 67601

Name of Party Responsible for Plugging Fees: Downing Nelson Oil Co., Inc.  
State of KS County, Ellis, ss.

Alan Downing (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Alan Downing  
(Address) P.O. Box 372 Hays, KS 67601



Subscribed and SWORN TO before me this 12 day of October, 2006  
Michele L Meier My Commission Expires: 7/28/09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 16 2006  
KCC WICHITA