

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-041-20,057-00-01

LEASE NAME Riordan OWWO

WELL NUMBER #5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330' Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 6 TWP. 15 RGE. 1 (S) or (W)

COUNTY Dickinson

EASE OPERATOR Bruce Oil Company
ADDRESS 1704 Limestone Road

PHONE# (620) 241-2938 OPERATORS LICENSE NO. 5610

Character of Well oil

Date Well Completed _____

Plugging Commenced 10-6-06

Plugging Completed 10-9-06

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-06-06 (date)

by Greg Evef (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 2590' Bottom 2662' T.D. 2662'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss	Oil & Water	surf	2661	4 1/2	2661'	1800'
		surf	N/A	8 5/8	N/A	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Sand to 2450 Put 4 S/K of C/m on sand. Rip casing at 1800'. Pull casing. Build plug at 260' Fill to surface with slurry cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address Box 341 Canton, KS 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lonny Bruce

STATE OF Kansas COUNTY OF McPherson, ss.

Lonny Bruce (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Lonny Bruce

(Address) McPherson, Kansas

SUBSCRIBED AND SWORN TO before me this 18 day of October, 19 2006

Beverly A. Folck
Notary Public

My Commission Expires: 12-13-09



Form CP-4
Revised 05-88

RECEIVED
OCT 19 2006
KCC WICHITA

PET

BM&S OIL
 BOX 316 #5 RIARDON "OWWO" 6-15-1E
 CANTON, KS. 67428 SW SW SW
 CONTR KANSAS DRLG. & WELL SERV. CTY. DICKINSON

GEOL HARRY HOPKINS FIELD ASH GROVE
 E 1320 KB CM 8/13/81 CARD ISSUED 10/15/81 IP P 4 BOPD & WTR
 MISS 2608-2616

+	+	+
+	+	+
+	+	+

API 15-041-20,057

LOG	TOPS	DEPTH	DATUM
FT R		357	+ 963
B FLOR FT		493	+ 827
WREF		555	+ 765
NEVA		773	+ 547
HOW		1415	- 95
TOP		1510	- 190
HEEB		1780	- 460
TOR		1803	- 483
DOUG		1815	- 495
IATAN		1907	- 587
LANS		1955	- 635
B KC		2325	-1005
CHER		2485	-1165
MISS WAR		2590	-1270
MISS OS		2655	-1335
MISS GC		2765	-1445

OLD INFO: OPERATOR WAS CARTER OIL CO.
 #6 STRAT TEST, SPD 1942, CSG NA,
 COMPLETED AS D&A/ARB

SO IN MISS
 NO DST'S

NEW INFO: RE-ENTERED 8/13/81, WSH
 DWN TO MISS, SET 4 1/2" 2661, MICT -
 CO, PF (MISS) 2608-16, SWB GSO,
 NAT, POP, P 4 BOPD & WTR, (GR 35°),
 10/5/81

KIND	2805-1485	SIMP	3340-2020
HUNT	2953-1633	ARB	3400-2080
SYL SH	3130-1810	TD	3449-2129
VIOLA	3230-1910		

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 OCT 19 2006
 KCC WICHITA