

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-041-20,045-00-00

LEASE NAME Riordan

WELL NUMBER # 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 6 TWP. 15 RGE. 1 (E) ###

COUNTY Dickinson

EASE OPERATOR Bruce Oil Company

ADDRESS 1704 Limestone Road

PHONE # (620) 241-2938 OPERATORS LICENSE NO. 5610

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 10-9-06

Plugging Completed 10-10-06

The plugging proposal was approved on 10-10-06 (date)

by Greg Evef (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 2587' Bottom 2663' T.D. 2663' 2636

Show depth and thickness of all water, oil and gas formations.

*KCC 10/20/06
PKT per RBDMS*

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss	Oil & Water	surf	2635'	4 1/2"	2635'	1200'
		surf	112'	8 5/8"	112'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand to 2500' 4 S/K OF C/M on sand Rip casing at 1200' Pull casing
Build plug at 260' Fill to Surface with slurry cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address Box 341 Canton, KS 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lonny Bruce

STATE OF Kansas COUNTY OF McPherson, ss.

Lonny Bruce (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lonny Bruce

(Address) McPherson, Kansas

SUBSCRIBED AND SWORN TO before me this 18 day of October, 2006

Beverly A. Folch
Notary Public

RECEIVED
OCT 19 2006
KCC WICHITA

My Commission Expires: 12-13-09

NOTARY PUBLIC
State of Kansas
BEVERLY A. FOLCH
My Appt. Expires 12-13-09

Form CP-4
Revised 05-88

PKT

BM&S OIL
 BOX 316
 CANTON, KS 67428
 #3 RIORDAN
 6-15-1E
 SW SE SW
 CONTR KS DRLG & WELL SVC CTY DICKINSON
 GEOL HARRY HOPKINS FIELD ASH GROVE
 E NA CM 9/13/80 CARD ISSUED 1/22/81 IP P 18 B0 & 90 BWPD
 MISS 2595-2600
 API 15-041-20,045

+	+	+
+	+	+

DL	TOPS	DEPTH	DATUM
LANS		1952	
KC		2194	
MISS CHT		2587	
MISS LM		2627	
RTD		2636	

8-5/8" 112/125sx, 4 1/2" 2635/180sx

NO DSTS
 MICT - CO, PF (MISS) 5/2595-2600, AC
 300 G (7 1/2%), SWB LD W/SO, POP, P 18
 B0 & 90 BWPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 OCT 19 2006
 KCC WICHITA