

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco Inc.
Address: PO Box 723 Hays, KS 67601
Phone: (785) 628-6101 Operator License #: 5363
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-17-06 (Date)
by: Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARB Depth to Top: 3652 Bottom: 56 T.D. _____
KC Depth to Top: 3399 Bottom: 3526 T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-02345-00-00
Lease Name: Bieker
Well Number: 4
Spot Location (QQQQ): SE - NW - NW -
4290 Feet from North / South Section Line
4290 Feet from East / West Section Line
Sec. 6 Twp. 11 S. R. 20 East West
County: Ellis
Date Well Completed: 2-12-57
Plugging Commenced: 10-17-06
Plugging Completed: 10-17-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	220'	8 5/8	2-12-57	-
		Surface	3660	5 1/2	2-12-57	-


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Move in plug string, Run tbg to 2000', Rig up Allied Cement. Mix 40 sks 60/40 pos 10% gel. pmp down 8 5/8. Fill cellar. Mix 180 sks at 2000' cir cmt to surface. Pull tbg. Hook up to 5 1/2. Mix 20 sks w/ 1 sk hulls. Press to 1200#. us 240 sks 60/40 10% gel.

Name of Plugging Contractor: Berexco Inc. Professional Pulling Services License #: 5363-32810
Address: PO Box 723 Hays, KS 67601
Name of Party Responsible for Plugging Fees: Curt Gabel Berexco
State of KS County, Ellis, ss. _____

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 723 Hays KS 67601



and SWORN TO before me this 18 day of October
Shanna Miller My Commission Expires: 9/19/09
Notary Public

RECEIVED
OCT 23 2006