

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.  
Address: PO Box 723 Hays, KS 67601  
Phone: (785) 628-6101 Operator License #: 5363  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9-26-06 (Date)  
by: Mike Maier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Ft. Scott Depth to Top: 4323 Bottom: 4344 T.D. \_\_\_\_\_  
Mississippi Depth to Top: 4221 Bottom: 4448 T.D. 4489  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-135-00519-00-01  
Lease Name: Ross Potter  
Well Number: 3  
Spot Location (QQQQ): SW - NE - NE - 10/24/06  
4290 Feet from  North /  South Section Line *KCC PPT Per PBDMS*  
990 Feet from  East /  West Section Line  
Sec. 26 Twp. 17 S. R. 25  East  West  
County: Ness  
Date Well Completed: 8-10-55 *original*  
Plugging Commenced: 9-26-06  
Plugging Completed: 9-28-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	237'	9 5/8	7/22/55	-
		surface	4489	5 1/2	8/5/1955	-


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/ catcher & release & TOH w/ lockset. TIH open tbg to 4450 pump 25 sks 60/40 6% w/ 100# hulls. Pull tbg to 3205 mix 50 sks common w/3% ccc.  
TOH w/ tbg Perf at 850' tie on to 5-1/2 csg & pmp 160 sks 60/40. Tie onto 9-5/8 & pmp 10 sks 60/40. Top of 5-1/2 w/ 35 sks 60/40 6%.

Name of Plugging Contractor: Professional Pulling Services License #: 32970 32810 *KCC 10/25/06 Per per SHANNA MILLER*  
Address: PO Box 486 Hays, KS 67601  
Name of Party Responsible for Plugging Fees: Berexco, Inc. Mark Leiker  
State of KS County, Ellis, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker  
(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 17 day of October, 2006 *PPT*  
Shanna Miller My Commission Expires: 9/19/09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 23 2006  
KCC, WICHITA