

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco, Inc.
Address: PO Box 723 Hays, KS 67601
Phone: (785) 628-6101 Operator License #: 5363
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-27-06 (Date)
by: Mike Maier and Eric MacLaren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Ft. Scott Depth to Top: 4308 Bottom: 4310 T.D. _____
Mississippi Depth to Top: 4406 Bottom: 44 T.D. 4492
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-00517-00-00
Lease Name: Ross Potter
Well Number: 1
Spot Location (QQQQ): SW - NW - NE - KCC
4290 Feet from North / South Section Line 10/24/06
2310 Feet from East / West Section Line PKT
Sec. 26 Twp. 17 S. R. 25 East West Per
County: Ness Figgs
Date Well Completed: 11-11-54 CPSD
Plugging Commenced: 9-27-06
Plugging Completed: 9-28-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	252'	9 5/8	10-21-54	-
		surface	4489	5 1/2	11-11-54	-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


TIH w/ 2 3/8 workstrg #37 to 3954' pmp 65 sks 60/40 6% gel w/ 300# hulls. Pull tbg to 1198' mix 60 sks common w/ 4% calcium.
TOH PSI csg to 500# tag cmt w/ perf gun 1175' perf at 1000' mix 205 sks 60/40 w/ 6% gel w/ 200 # hulls (80 over csg vol)
Pmp dwn 5 1/2 and shut it 300# mix 100 sks 60/40 6% w/ 100# hulls. Shut in at 100 psi.

Name of Plugging Contractor: PPS Professional Plugging Services License #: 32810 32970 5363 KCC PKT
Address: PO Box 486 Hays, KS 67601 10/24/06
Name of Party Responsible for Plugging Fees: Berexco, Inc. Mark Leiker per oper.
State of KS County, Ellis, ss. Shanna Miller

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Shanna Miller

(Address) PO Box 723 Hays, KS 67601



My Commission Expires: 9/19/09 17 day of October, 20 06

Shanna Miller My Commission Expires: 9/19/09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 23 2006
KCC WICHITA