

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Fremont Exploration, Inc.
 Address: 12412 St. Andrews Dr., Oklahoma City, OK 73120
 Phone: (405) 936-0012 Operator License #: 31790
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 9/27/06 (Date)
 by: Ed Schumacher (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-23226-00-00
 Lease Name: Pfeifer
 Well Number: 17-1
 Spot Location (QQQQ): _____ - NW - SE - NW
1965 Feet from North / South Section Line
1487 Feet from East / West Section Line
 Sec. 17 Twp. 9 S. R. 25 East West
 County: Graham
 Date Well Completed: 9/28/06
 Plugging Commenced: 9/28/06
 Plugging Completed: 9/29/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	261'	8 5/8	261'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging commenced 9/28/06 @ 10:30 pm, 25 sx @ 2320', 100 sx @ 1415', 40 sx @ 310', 10 sx @ 40', 15 sx Rathole - - Total of 190 sx
 60/40 poz - - 6% gel - - 1/4# per sx flo-seal, Job completed @ 1:30 am, 9/29/06 by Allied Cementing

Name of Plugging Contractor: WW Drilling, LLC License #: 33575
 Address: P.O. Box 307, WaKeeney, KS 67672

Name of Party Responsible for Plugging Fees: Fremont Exploration, Inc. - Tom Conroy
 State of Oklahoma County, Oklahoma, ss.

Tom Conroy (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Sam Conroy
 (Address) 12412 St. Andrews Dr., Oklahoma City, OK 73120

SUBSCRIBED and SWORN TO before me this 17th day of October, 2006

Sandy Savard My Commission Expires: 7-27-08
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 23 2006
KCC WICHITA