

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20753-0000

LEASE NAME JARVIS

WELL NUMBER 3-35

1250' FSL Ft. from S Section Line

2550' FEL Ft. from E Section Line

SEC. 35 TWP. 29S RGE. 37W (E) or (W)

COUNTY GRANT

Date Well Completed 04/04/88

Plugging Commenced 10/04/06

Plugging Completed 10/05/06

*NWNWSWSE
KCC per 10/25/06
per CH*

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09/25/06

by DAVID WILLIAMS

RECEIVED

OCT 24 2006

KCC WICHITA

(KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3102' Bottom 3000' T.D. 2902'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2433'	2670'	8 5/8"	710'	0'
				5 1/2"	2997'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

10/05/06 Witnessed by J Holland, KCC.CIBP @ 2400'. NU cmtr to 5 1/2" csg. pmp 10 bbl mud & 25 sx cmt plug 1740' to 1540' & 36 bbl mud. Circ hole w/40 bbl mud & 50 sx cmt plug 740'to 590'& 14 bbl mud. Load hole w/3 bbl mud to 40' & 10 sx cmt 40' - 0'. Cut 5 1/2" csg & 8 5/8" surf csg @ 3' bgl, weld on trash cover - ID plate.'

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



ANGIE G. HERNANDEZ
Notary Public, State of Texas
My Commission Expires
JULY 14, 2009

SUBSCRIBED AND SWORN TO before me this 12th day of October, 2006

My Commission Expires: 7/14/2009

Angie G Hernandez
Notary Public

per