

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Great Plains Energy, Inc.
Address: PO Box 292, 429 N. Linden, Wahoo, Nebraska 68066
Phone: (402) 277-5336 Operator License #: 33629
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3/30/06 (Date)
by: Herb Dienes (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 137-20452-0000
Lease Name: Harting
Well Number: 1
Spot Location (QQQQ): NE - SW - SW - SW
595 Feet from North / South Section Line
370 Feet from East / West Section Line
Sec. 33 Twp. 3 S. R. 23 East West
County: Norton
Date Well Completed: 3/31/06
Plugging Commenced: 3/31/06
Plugging Completed: 4/1/06


KCC
PKT
per
C-1
10/25/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	392'	8 5/8"	392	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Plugging commenced @10:00 pm on 3/31/06. 25sx @ 3800', 25 sx @ 2100', 100 sx @ 1325', 40 sx @ 425', 10 sx @ 40', 10 sx in mousehole, 15 sx in rathole. 225 sx total. 60/40 poz, 6% gel, 1/4# per sx flo seal. Job completed @ 3:00am on 4/1/06.

Name of Plugging Contractor: Kaler Oil Company License #: 33607
Address: PO Box 370, Gainesville, Texas 76241
Name of Party Responsible for Plugging Fees: Great Plains Energy, Inc.
State of Nebraska County, Saunders, ss.
Dan Blankenau (Employee of Operator) or (Operator) on above-described well, being first duly



sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, before me.
(Signature) _____
(Address) PO Box 292, Wahoo, Nebraska 68066

SUBSCRIBED and SWORN TO before me this 6th day of October, 2006
Carol A. Medina My Commission Expires: Feb 10, 2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 19 2006
KCC WICHITA