

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-207-27045-00-00 Please TYPE Form and File ONE Copy

API # 15-207-27045-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date June 29, 2006.

Well Operator: Nordmeyer Oil Inc (Owner/Company Name) KCC License #: 6788 (Operator's)

Address: 362 90th Road City: Toronto

State: Kansas Zip Code: 66777 Contact Phone: (620) 637-2964

Lease: Nordmeyer Well #: 2 Sec. 14 Twp. 25 S. R. 13 East West

NE 1/4 Sec. 14 Spot Location / QQQQ County: Woodson

2185 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2048 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # Na ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 40 ft. Cemented with: 15 Sacks

Production Casing Size: None Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: Na (G.L. / K.B.) T.D.: 1525 PBDT: 1475 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Put in 15 sacks of 60/40

Pozmix cement through drill pipe 1525 ft. pulled pipe 493 ft. ran 15 sacks in the Kansas city zone. 55 sacks 250 ft. to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rig 6 Drilling Co. Inc.

Bud Sifers Phone: (620) 365-6294

Address: Po. Box 227 Iola City / State: Kansas 66749

Plugging Contractor: Rig 6 Drilling Co. KCC License #: 30567 (Contractor's)

Address: Po. Box 227 Iola, Kansas 66749 Phone: (620) 365-6294

Proposed Date and Hour of Plugging (if known?): June 29, 2006. 1:30 PM.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Sept. 16, 06 Authorized Operator / Agent: _____ (Signature)

* Well already plugged - KCC - Dg
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 10 2006
KCC WICHITA

Rig 6 Drilling Co. Inc.

PO Box 227
Iola, Kansas 66749

Bud Sifers
620.365.6294

John Barker
620.365.7806

Company: Nordmeyer Oil Co
Address: 362 90 th rd
Toronto,KS 66777
Lease: Nordmeyer
County: Woodson
Location: 2185 FSL/2048 FEL
14/25/13c

Commenced: 6/24/06
Completed: 6/27/06
Well #: 2
API #: 15-207-27045
Status: Dry Hole
Total Depth: 1525'-6 3/4"
Casing: 40'-8 5/8'cmt w/ 15 sx

Driller's Log:

11	Soil & Clay	1084	Sh w/ ls strks
23	Sa	1089	Ls
30	Sh	1093	Sh (blk)
63	Ls	1175	Ls w/ sh brks
79	Sh w/ sa sh	1339	Sh w/ ls strks
182	Sh	1346	Sa (no odor ,no show
201	LS w/ sh brks	1510	Sh
372	Sh	1525	Ls T.D.
491	Ls		
633	Sh		
649	Ls w/ sh strks		
578	Sh		
840	Ls w/ sh brks		
983	Sh (sandy)		
987	Ls		
1012	Sh		
1023	Ls		

Plugging Report:

50' @ T.D.
50' @ Base KC (500'
250' to surface

4:30 to 6:00 pm 6/27
Taylor @ Chanute gave permission to plug.
Consolidated Cement

RECEIVED
OCT 10 2006
KCC WICHITA

CONSOLIDATED OIL WELL SERVICES, INC.
 P.O. BOX 884, CHANUTE, KS 66720
 620-431-9210 OR 800-467-8676

TICKET NUMBER 10231
 LOCATION EUREKA
 FOREMAN Kevin McCoy

TREATMENT REPORT & FIELD TICKET
 CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6-27-06	8001	Nordmeyer #2	14	25S	13E	Woodson
CUSTOMER Nordmeyer Oil Inc.			Rig 6 Delq.			
MAILING ADDRESS 362 90 th Rd						
CITY Toronto	STATE Ks	ZIP CODE 66777				
TRUCK # DRIVER TRUCK # DRIVER						
			445	Rick L.		
			442	Rick P.		

JOB TYPE P.T.A. HOLE SIZE 6 3/4 HOLE DEPTH 1525' CASING SIZE & WEIGHT _____
 CASING DEPTH _____ DRILL PIPE 3 1/2 TUBING _____ OTHER _____
 SLURRY WEIGHT 13.6 # SLURRY VOL _____ WATER gal/sk 6.7 CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Rig up to 3 1/2 DRILL Pipe. Spot Cement Plugs As Following.

15 sks @ 1525'
15 sks @ 493'
55 sks 250' to SURFACE
85 sks TOTAL

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 N	1	PUMP CHARGE	800.00	800.00
5406	20	MILEAGE	3.15	63.00
1131	85 sks	60/40 Pozmix Cement	9.35	794.75
1118 A	300 #	GeL 4%	.14	42.00
5407	3.65 TONS	TON Mileage BULK TRUCK	MIC	275.00
RECEIVED				
OCT 10 2005				
KCC WICHITA				
			Sub Total	1974.75
			SALES TAX	52.72
			ESTIMATED TOTAL	2027.47

THANK YOU

6.3%

200512

AUTHORIZATION Called By Bud

TITLE Rig 6 Delq.

DATE _____