

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 007-22,673-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056
(Owner/Company Name) (Operator's)
Address: 9431 E. Central, St. 100 City: Wichita
State: KS Zip Code: 67206 Contact Phone: (316) 684 - 8481
Lease: HICKS-JOHNSON Well #: 1-10 Sec. 10 Twp. 30 S. R. 14 East West
NE - NE - NW Spot Location / QQQQ County: Barber

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 13-3/8" Set at: 231'KB Cemented with: 275 Sacks
Production Casing Size: 4-1/2" Set at: 3507' Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: Howard: 3114' - 3421', Bern Ls: 3318' - 3322', 3300' - 3304'.

Elevation: 1960/1969 (G.L. / K.B.) T.D.: 4740' PBDT: 3477' Anhydrite Depth: 813'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Heavy Mud, hulls, cement and plug according to KCC regulations.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rob Long

Phone: (620) 793 - 0915/564 - 3831

Address: P.O. Box 308 City / State: Ellinwood, KS. 67526

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/16/2006 Authorized Operator / Agent: _____

Loveness Mpanje
Loveness Mpanje
(Signature)

RECEIVED
OCT 17 2006

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Hicks-Johnson No. 1-10

LOCATION: C Ne Ne Nw Section 10 T 30s R 14w
API: 15-007-22673-0000 Barber County, Kansas

OWNER: F.G. Holl Company, L.L.C.

COMMENCED: 28-Aug-01

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 13-Sep-01

TOTAL DEPTH: DRILLER 4740 FEET
LOGGER 4743 FEET

Ground Elevation: 1960

KB Elevation: 1969

LOG

0 -	3 FEET	Top Soil
3 -	30 FEET	Clay
30 -	45 FEET	Sandy Clay
45 -	70 FEET	Sand and Gravel
70 -	85 FEET	Clay
85 -	115 FEET	Sand and Gravel (Shale Below)
115 -	797 FEET	Redbeds
797 -	813 FEET	Anhydrite (Log)
813 -	1986 FEET	Redbeds, Shales and Salt
1986 -	4647 FEET	Limestone, Shale and Dolomite
4647 -	4740 FEET	Arbuckle

CASING RECORDS

Surface Casing 13-3/8"

Spud at 6:30 am on 8/28/01. Drilled 17-1/2" hole to 235'. Ran 6 joints of new 48# 13-3/8" surface casing, tally 219.54' set at 231' KB. Cemented with 275 sx 60/40 Poz, 2% Gel, 3% CC.
Plug down at 1:30 pm on 8/28/01 by Acid Services. Ticket #03827. Cement did circulate.

Production Casing

Plugged Arbuckle with 40 sx 60/40 Poz 6% Gel. Plug at 4642'. Plug down at 11:30 am on 09/13/01 by Allied. Ticket # 03977.

Ran 87 joints of 10.5#, 4-1/2" casing. Tallied 3507' and set at 3507' KB.

Cemented with 125 sx 50/50 Poz and 50 sx Lite. Plug down at 9:45 pm on 09/13/01 by Allied. Ticket #03978. Cemented rathole with 15 sx, mousehole with 10 sx.

DEVIATION SURVEYS

1/2 degree(s) at	235	feet
3/4 degree(s) at	950	feet
1/2 degree(s) at	3071	feet
1-1/2 degree(s) at	4208	feet
3/4 degree(s) at	4472	feet
1-1/4 degree(s) at	4553	feet

RECEIVED
OCT 17 2006
KCC WICHITA

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

October 19, 2006

Re: HICKS-JOHNSON #1-10
API 15-007-22673-00-00
NENENW 10-30S-14W, 330 FNL 2310 FWL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888