

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 067-20,626-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 10/21/86

Well Operator: Hartman Oil Co., Inc. KCC License #: 30535
(Owner / Company Name) (Operator's)

Address: 12950 E. 13th St. N. City: Wichita

State: Ks. Zip Code: 67203-1457 Contact Phone: (620) 277 - 2511

Lease: Fry Well #: #1 Sec. 21 Twp. 28 S. R. 35 East West

E/2 - W/2 - NE/4 Spot Location / QQQQ County: Grant

3960 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

Surface Casing Size: 8-5/8" Set at: 1832' Cemented with: 575 Sacks

Production Casing Size: 5-1/2" Set at: 3046' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2955-58' - 2931-35' - 2893-98' Council Grove

Elevation: 3059' (G.L. / K.B.) T.D.: _____ P.B.T.D.: _____ Anhydrite Depth: 1795'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As Per KCC - Jim Holland - Set CIBP @ 2885' w/ 2 sks cmt
Run free point - cut off csg @ 1800' - recover csg - RIH w/ tbg - spot 1st Plug @ 1850' w/ 50 sks 60-40 poz w/6% gel - spot 2nd
Plug @ 700' w/ 60-40 poz w/ 6% - spot 3rd Plug @ 60' w/ 60-40 poz w/ 6% gel - cap off 8-5/8"

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: STAN MITCHELL

Hartman Oil Co., Inc. Phone: (620) 277 - 2511

Address: 4550 W 9 MI RD - GARDEN CITY City / State: KS.

Plugging Contractor: ALLIED KCC License #: 30535
(Company Name) (Contractor's)

Address: P O BOX 27 - OAKLEY, Ks. Phone: (785) 672 - 3452

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/29/06 Authorized Operator / Agent: A.T. Mitchell 9/29/06
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT - 2 2006
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Hartman Oil Co., Inc.
12950 E. 13th
Wichita, KS 67230

October 10, 2006

Re: FRY #1
API 15-067-20626-00-00
E2W2NE 21-28S-35W, 3960 FSL 1650 FEL
GRANT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888