

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02662-00-00
Spot: E2SESW Sec/Twnshp/Rge: 3-13S-17W
660 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SCHMEIDLER Well #: 1
County: ELLIS Total Vertical Depth: 3540 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: 1008 CODY AVENUE PO BOX 550
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3536	0	w/100 sxs cmt
SURF	8.625	155	0	w/80 sxs cmt

115.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2006 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL INC. Phone: (785) 625-5327

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing parted at 464'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3010' - mixed and pumped 260 sxs cement with 500# hulls - circulated cement up 5 1/2" x 8 5/8".
POOH. Swaged onto 5 1/2" and topped with 25 sxs cement.
S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3536	3540	OH	Arbuckle
3463	3465		
3443	3447		
3364	3367		
3334	3338		
3306	3310		
3282	3286		
3260	3264		

INVOICED
DATE 10-19-06
WT. NO. 2007060725

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

AD

Signed

(TECHNICIAN)

OCT 16 2006

RECEIVED

Form CP-2/3

OCT 18 2006

KCC WICHITA

LEO J. DREILING

#1 SCHMEIDLER

3-13-17W
E2 SE SW

Contr. CO TOOLS

ELLIS County

E 2033 KB Comm. 8/5/62 Comp. 9/13/62 IP 52 BOPD, NW/ARB
(3536-40) GR 30

Tops	Depth	Datum
ANHY	1198	+835
TOP	2093	-60
HEEB	3233	-1200
TOR	3258	-1225
LANS	3281	-1248
ARB	3534	-1501
TD	3540	-1507

Casing


8" 155/100 sx
5" 3536/100 sx:

DST 3289-3340/60", GD BLO, 70' GAS, 30' O & GCM, 120' SO & GCM, FBHP 186#/20", FP 74-119#:

DST 3361-3387/60", 180' GAS, 45' O & GCM, 75' SO & GCM, FBHP 440#/20", FP 44-89:
CO 3540, FU 1500' OIL, SWB 3 BOPD, NW 5/HRS,
NAIL: PMP 30 BOPD, NW:

NO LOGS:

CATHERINE



C. STEINCAMP, GEOL.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS