

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02345-00-00
Spot: SENWNW Sec/Twnshp/Rge: 6-11S-20W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BIEKER Well #: 4
County: ELLIS Total Vertical Depth: 3660 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	3350		
PROD	5.5	3660	0	150 SX CMT
SURF	8.625	220	0	150 SX CMT

\$ 118.95

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2006 11:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURTIS GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeeze jobs: 843' w/500 sxs; 870' w/300 sxs; 1230' w/300 sxs.
CIBP at 3350'.
Prior operator dropped 4 1/2" liner while running in the hole. Top 4 1/2" liner 2019'. Unable to get below 3054'.
Decided to P/A.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2006 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2020'. Allied pumped 180 sxs 60/40 pozmix - 10% gel - neat - circulated cement.
PTOH. Squeezed 5 1/2" casing with 20 sxs cement.
Max. P.S.I. 1200#. Blew 2" bull plug outside of casing.
Hole full of cement.
Hooked up to backside. Allied pumped 40 sxs cement.
Backside full of cement - cellar full. Hole in 8 5/8" 3' down.

Perfs:

Top	Bot	Thru	Comments
3652	3656		
3632	3635		
3521	3526		
3504	3507		
3483	3487		
3409	3412		
3399	3402		

INVOICED

DATE 10-23-06
INV. NO. 2007060727

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

HTD.

Signed

Richard Williams

(TECHNICIAN)

OCT 18 2006

Form CP-2/3

PKT

6-11-20W
SE NW NW

HERMAN GEO KAISER #4 BLEKER

Contr. VEEDER SUP & DEVE ELLIS County

E 2049RB Comm. - Comp. 4-12-57 IP 220 BOPD/ARB
PHY POT

Tops	Depth	Datum
EST Arch	1490	+ 559
HEEB	3285	-1236
LANS	3320	-1271
B/KC	3545	-1496
CONG	3580	-1531
ARB	3625	-1576
TD	3660	-1611

Casing
8" 220
5" 3660

PERF 3652-56: ACID 1000
8 BOPH

TRICO POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS