

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20109-00-00
Spot: E2SWSWSW Sec/Twnshp/Rge: 33-6S-21E
331 feet from S Section Line, 561 feet from W Section Line
Lease Name: SMITH H Well #: 2
County: ATCHISON Total Vertical Depth: 1582 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1588	0	153 SX CMT
SURF	8.625	168	0	70 SX CMT

\$ 51.42

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/08/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1546' TO 1370'. CEMENT FROM 1370' TO 1125'. GEL FROM 1125' TO 175'. CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL
Date/Time Plugging Completed: 03/08/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1540' and then pumped 13 barrels of gel. Had gel from 1540' to 1381'. Pulled the tubing up to 1381' and pumped 11 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. Cement was placed from 1381' to 1125' and gel from 1125' to 275'. Pulled the tubing up to 275' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1319	1320		
1304	1306		
1250	1255		
1194	1205		
1185	1186		
1175	1176		

RECEIVED
KCC DISTRICT #3

OCT 13 2006 TCH

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2006
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 10-23-06
INV. NO. 2007060728

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C Herman

(TECHNICIAN)

PEP