

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20110-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 33-6S-21E  
1193 feet from S Section Line, 1225 feet from E Section Line  
Lease Name: BOLDRIDGE C Well #: 1  
County: ATCHISON Total Vertical Depth: 1530 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1524	0	150 SX CMT
SURF	8.625	158	0	175 SX CMT \$149.73

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1490' TO 1444'. CEMENT FROM 1444' TO 1140'. GEL FROM 1140' TO 175'. CEMENT 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/07/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1490' and then pumped 10 barrels of gel from 1480' to 1440'. Pulled the tubing up to 1440' and pumped 11.5 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. Cement was placed from 1440' to 1136' and gel from 1136' to 275'. Pulled the tubing up to 286' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1393	1394		
1389	1390		
1344	1346		
1330	1332		
1270	1275		
1198	1199		
1190	1191		

INVOICED  
DATE 10-23-06  
BY NO 2007060728

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 20 2006  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Howman  
(TECHNICIAN)

Rec'd Dist 3  
10/13/06

PRT