

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20112-00-00
Spot: NESWNW Sec/Twnshp/Rge: 4-7S-21E
1556 feet from N Section Line, 1013 feet from W Section Line
Lease Name: WALNUT Well #: 4-2
County: ATCHISON Total Vertical Depth: 1500 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1492	0	163 SX CMT
SURF	8.625	223	0	105 SX CMT

\$ 48.75

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/27/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1458' TO 1359' CEMENT FROM 1359' TO 1110', GEL FROM 1110; ' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/27/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1450' and then pumped 10.5 barrels of gel from 1450' to 1355'. Pulled the tubing to 1355' and pumped 11 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. Cement was placed from 1355' to 1093' and gel from 1093' to 275'. Pulled the tubing to 286' and circulated 35 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1307	1309		
1290	1292		
1239	1243		
1160	1162		

RECEIVED
KCC DISTRICT #3

OCT 13 2006 TCH

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2006
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks:

Plugged through: TBG

DATE 10-23-06
WV. NO 2007060728

District: 03

Signed

Taylor C. Herman
(TECHNICIAN)

PET