

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20113-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 4-7S-21E
875 feet from S Section Line, 606 feet from W Section Line
Lease Name: WALNUT Well #: 4-3
County: ATCHISON Total Vertical Depth: 1659 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1651	0	150 SX CMT
SURF	8.625	217	0	95 SX CMT

\$ 53.92

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/28/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GELFROM 1622' TO 1542', CEMENT FROM 1542 TO 1236', GEL FROM 1236' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 02/28/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1600' then pumped 10.75 barrels of gel from 1600' to 1537'.
Pulled the tubing up to 1537' and pumped 14 barrels of gel and 35 sacks of cement with 1 sack of cottonseed hulls. The cement was placed from 1537' to 1233' and gel from 1233' to 275'.
Pulled the tubing up to 286' and circulated 35 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1489	1492		
1446	1448		
1441	1443		
1384	1385		
1373	1376		
1302	1303		
1294	1295		
1286	1288		

RECEIVED
KCC DISTRICT #3

OCT 13 2006

CHANUTE, KS

TCH

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED
DATE 10-23-06
2007060728

PPT