

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20114-00-00  
Spot: E2SWSWSE Sec/Twnshp/Rge: 4-7S-21E  
330 feet from S Section Line, 2151 feet from E Section Line  
Lease Name: WALNUT Well #: 4-4  
County: ATCHISON Total Vertical Depth: 1515 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

| String | Size  | Depth (ft) | Pulled (ft) | Comments   |
|--------|-------|------------|-------------|------------|
| PROD   | 5.5   | 1501       | 0           | 153 SX CMT |
| SURF   | 8.625 | 155        | 0           | 150 SX CMT |

# 49.24

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1466' TO 1397' CEMENT FROM 1397' TO 1146', GEL FROM 1146' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 03/01/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1460' and then pumped 10 barrels of gel from 1460' to 1397'. Pulled the tubing up to 1397' and pumped 10 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. The cement was placed from 1397' to 1135' and gel from 1135' to 275'. Pulled the tubing up to 273' and circulated 30 sacks of cement to surface.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1345 | 1347 |      |          |
| 1333 | 1335 |      |          |
| 1278 | 1280 |      |          |
| 1275 | 1276 |      |          |
| 1202 | 1203 |      |          |
| 1196 | 1198 |      |          |

RECEIVED  
KCC DISTRICT #3

OCT 13 2006 TCH

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 20 2006  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

INVOICE  
DATE 10/23/06  
# 2007060728

PRG