

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20115-00-00
Spot: E2W2SWSE Sec/Twnshp/Rge: 5-7S-21E
685 feet from S Section Line, 2154 feet from E Section Line
Lease Name: WALNUT Well #: 5-1
County: ATCHISON Total Vertical Depth: 1585 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1580	0	158 SX CMT
SURF	8.625	233	0	112 SX CMT

\$ 51.51

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1535' TO 1479', CEMENT FROM 1479' TO 762', GEL FROM 762' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL
Date/Time Plugging Completed: 03/16/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1440' and then pumped 11 barrels gel and 80 sacks of cement with 2 sacks of cottonseed hulls. The cement was placed from 1440' to 740' and gel from 740' to 284'. Pulled the tubing up to 280' and circulated 30 sacks of cement to surface.

RECEIVED
KCC DISTRICT #3
OCT 13 2006 TCH
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1427	1429		
1403	1409		
1344	1350		
1260	1265		
1071	1081		
1056	1062		
1033	1038		
1001	1005		
944	950		
905	911		
812	818		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 20 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED
DATE 10/23/06
INV. NO. 2007060728

PLC