

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24214-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 27-19S-19E  
2300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: KUESER Well #: 27-43  
County: ANDERSON Total Vertical Depth: 1220 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1192		165 SX
SURF	8.625	21		4 SX

\$ 39.65

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 800'; CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 800' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 05/25/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO 1150 FT. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING, TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF 60/40 POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1131	1132		
1126	1129		
1119	1123		
1085	1088		
1073	1076		
1065	1067		
1046	1047		

RECEIVED  
KCC DISTRICT #3

OCT 17 2006 FG

CHANUTE, KS

INVOICED  
DATE 10/24/06  
INV. NO. 2007060735

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

Form CP-2/3

RECEIVED  
OCT 23 2006  
KCC WICHITA

PET