

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24219-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 27-19S-19E
830 feet from S Section Line, 1673 feet from E Section Line
Lease Name: KUESER Well #: 27-34
County: ANDERSON Total Vertical Depth: 1172 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1165		165 SX
SURF	8.625	20		4 SX

\$ 38.09

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2006 10:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: TRACKER RESOURCE DEVELOPM Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 500';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: NONE
Date/Time Plugging Completed: 06/07/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 135 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1101	1104		
1096	1099		
1090	1093		
1058	1061		
1020	1022		
881	883		
867	869		
838	844		
825	830		
649	653		

RECEIVED
KCC DISTRICT #3

OCT 17 2006 FG

CHANUTE, KS

INVOICED
DATE 10/24/06
2007060735

Remarks: OPERATER PLUGGED WELL

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
OCT 23 2006
KCC WICHITA

Form CP-2/3

PJT