

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24221-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 26-19S-19E  
710 feet from N Section Line, 330 feet from W Section Line  
Lease Name: KUESER Well #: 26-11  
County: ANDERSON Total Vertical Depth: 1209 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1200		165 SX
SURF	8.625	20		4 SX
T1	2.875	1136		

\$ 39.29

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 500';  
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 500' TO 4' BELOW GROUND LEVEL; CUT CASING AND  
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 06/06/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 122 SACKS OF POZ MIX FROM TD TO SURFACE. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1134	1138		
1130	1132		
1122	1128		
1117	1121		
1082	1084		
1055	1057		
1009	1011		
920	922		
896	899		
882	885		
875	877		
852	855		
839	841		
763	766		
739	742		
691	693		
657	661		

RECEIVED  
KCC DISTRICT #3

OCT 17 2006

FG

CHANUTE, KS

INVOICED

DATE

10/24/06

NO. 2007060735

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

RECEIVED  
OCT 23 2006  
KCC WICHITA

PPT