

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-181-00027-00-00

WELL PLUGGING RECORD

NORTH

		o	

Locate well correctly on above  
Section Plat

Sherman County, Sec. 11 Twp. 9S. Rge. 39 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Badger Driller's, Inc.  
Lease Name House Well No. 1  
Office Address Box 287, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 5, 1959  
Application for plugging filed August 5 1959  
Application for plugging approved August 5 1959  
Plugging commenced @ 11:00 a.m., August 5 1959  
Plugging completed @ 2:00 p.m., August 5 1959  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricus, Hill City, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5550 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	340	8 5/8	340	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1. Hole filled with heavy mud to 600 feet
2. Bottom plug placed @ 600 feet; 20 sacks cement displaced through drill pipe
3. Hole filled with heavy mud to 340
4. Center plug placed @ 340feet; 20 sacks cement displaced through drill pipe
5. Hole filled with heavy mud to 40 feet.
6. Top plug placed @ 40 feet; 10 sacks cement displaced through drill pipe

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1959  
08-17-1959  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Badger Driller's, Inc.,  
Address Box 287, Tulsa, Oklahoma

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
Fred A. Veail (~~Employer or owner~~ owner & operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred A. Veail  
Box 287, Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 14<sup>th</sup> day of August, 1959  
Martha Maher

My commission expires 6-26-60 Notary Public.

PLUGGING  
FILE SEC 11 T 9 R 39 W  
BOOK PAGE 69 LINE 22

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-181-00027-00-00

Company- BADGER DRILLERS, INC.  
Farm- House No. 1

SEC. 11 T. 9 R.39W  
NW NW SE

Total Depth. 5550'

Comm. 8-1-59

Comp. 8-14-59


Shot or Treated.

Contractor.

Issued. 5-6-61

County Sherman

KANSAS



CASING:  
8" 340'

Elevation. 3622'

Production. Dry

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

TOPS: SCOUT

Howard	4104
Topeka	4133
Heebner	4278
Toronto	4313
Lansing	4329
Base Kansas City	4674
Marmaton	4686
Cherokee	4825
Mississippi	5086
Arbuckle	5484

Total Depth 5550