

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sherman

County. Sec. 12 Twp. 9 Rge. 38 (E) (W) W

Location as "NE/CNW/SW" or footage from lines CSW SW SE

Lease Owner Phillips Petroleum Company

Lease Name Cress Well No. 1

Office Address Goodland, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Jan. 14, 1958 19

Application for plugging filed Jan. 14, 1958 19

Application for plugging approved Jan. 14, 1958 19

Plugging commenced Jan 15, 1958 19

Plugging completed Jan. 15, 1958 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5750 Ft. Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gun pits and place heavy mud in the hole.  
Run 25 sacks of cement from 3110 ft. to 3020 ft.  
This would be a 90 ft. plug from 40 ft. ~~xx~~ in the anhydrite to 50 ft in the red shale.  
Come up the hole to 275 ft and run 30 sacks of cement.  
This would be a 100 ft. plug from 275 ft. to 175 ft., or 50 ft. below the casing to 50 ft. in the casing.  
Run 10 sacks from 30 ft. to surface.

05-26-1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton  
Address Hill City, Kansas

STATE OF Kansas, COUNTY OF Sherman, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) J. H. Smith

SUBSCRIBED AND SWORN TO before me this 24 day of May, 1958  
J. H. Smith  
(Address)  
My commission expires June 18 - 1960  
J. H. Smith  
Notary Public.

PLUGGING  
FILE SEC. 12 T. 9 R. 38W  
BOOK PAGE 78 LINE 15