


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sherman County, Sec. 24 Twp. 9S Rge. 37W ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name Richard Well No. 1
Office Address 301 S. Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 21, 1965
Application for plugging filed July 21, 1965
Application for plugging approved July 21, 1965
Plugging commenced July 21, 1965
Plugging completed July 21, 1965
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugo Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4993 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	235'	8-5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4993'-700' Mud
700'-696' Plug
696'-656' Cement, 25 sacks
656'-250' Mud
250'-246' Plug
246'-206' Cement, 25 sacks
206'-40' Mud
40'-36' Plug
36'-6' Cement, 15 sacks
(Bottom of cellar)

RECEIVED
STATE CORPORATION COMMISSION
AUG 2 - 1965
08-02-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lauck Drilling Company, Incorporated
Address 301 S. Broadway, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
301 S. Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1965

My commission expires March 12, 1967

Stella J. Lippis
Notary Public.

15-181-~~1000~~⁰⁰⁰³⁴-00-00

D. R. Lauck Oil Company, Inc.

Richard #1

C SW NE Sec. 24-9S-37W
Sherman County, Kansas

Commenced: July 7, 1965
Completed: July 21, 1965

Casing Record: 235' 8-5/8" Cemented with 170 sacks Cement,
4 sacks Calcium Chloride.

Elevation: 3458 GL; 3461 DF; 3463 KB.

Drillers Log

Tops

Surface Clay	60
Sand	156
Sand & Clay	215
Blue Shale	234
Shale	1275
Sand	1325
Shale	1900
White Sand & Shale	2032
Sand & Shale	2120
Shale, Sand & Bentonite Streaks	2280
Shale	2310
Anhydrite	2352
Shale & Shells	2735
Shale & Lime	2910
Shale, Red Bed & Shells	3145
Shale, Shells & Lime	3350
Red Bed, Shale & Shells	3565
Lime & Shale	3770
Shale & Lime	3855
Lime & Shale	4120
Shale & Lime	4223
Lime & Shale	4292
Lime	4835
Lime & Chert	4857
Sand & Lime	4862
Lime, Sand & Shale	4914
Lime, Shale & Sand	4931
Lime	4980
Mississippian	4993 RTD

	<u>Samples</u>	<u>Welex</u>
Heebner	4168 -705	4168 -705
Toronto	4195 -732	4198 -735
Lansing	4218 -755	4216 -753
Base Kansas City	4549-1086	4546-1083
Marmaton	4572-1109	4568-1105
Cherokee	4695-1232	4694-1231
Morrow Sand	4845-1382	4847-1384
Mississippian (St. Louis)	4934-1471	4937-1474
Spergen	4972-1509	4974-1511
Total Depth	4993-1530	4991-1528

DST #1 (S) 4410-4460, open 30 minutes,
weak blow 4 minutes. Recovered
10' mud with few specks oil.
ISIP 1217#/20 min.
FSIP 1115#/20 min.
IFP 19#
FFP 38#

D&A

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 - 1965
08-02-1965
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct
log of the above mentioned well, to the best
of my knowledge and belief.

John A. Knightley
Subscribed and sworn to before me this

30th day of July, 1965

Stella J. Lips
Notary Public

My commission expires 3-12-67