


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-181-00028-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Sherman County, Sec. 35 Twp. 9S Rge. 40 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner **Badger Drillers, Inc.**
Lease Name **Murray** Well No. **1**
Office Address **Box 287, Tulsa, Oklahoma**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed **October 14** 19 **59**
Application for plugging filed **October 14** 19 **59**
Application for plugging approved **October 14** 19 **59**
Plugging commenced **9 a.m. October 14** 19 **59**
Plugging completed **12 Noon October 14** 19 **59**
Reason for abandonment of well or producing formation **Dry Hole**

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Fabricus**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **5280** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
0 - 40	Surface soil					
40 - 265	Clay & Shale	0	265	8-5/8	265	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 550'
Halliburton plug @ 550'
20 sax cement mixed through drillpipe placed on plug
Heavy mud to 260'
Plug @ 260' - 20 sax cement mixed through drillpipe placed on plug
Heavy mud to 40', plug @ 40', 10 sax cement on plug to base of cellar

CONSERVATION COMMISSION
OCT 28 1959
10-28-1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor **Badger Drillers, Inc.**
Address **Box 287, Tulsa, Oklahoma**

STATE OF **Oklahoma**, COUNTY OF **Tulsa**, ss.
Fred A. Veail

(Employer, owner, operator or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Fred A. Veail*
Box 287, Tulsa, Oklahoma

SUBSCRIBED AND SWORN TO before me this **19th** day of **October**, 19**59**

My commission expires **Sept. 28, 1961**

Doris M. Yocham
Doris M. Yocham Notary Public.



15-181-00028-00-00

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JAMES OIL
Farm- Murray

No. 1

SEC. 35 T. 9 R. 40W
C SW SE

Total Depth. 5280'

Comm. 10-1-59


Comp. 10-23-59

Shot or Treated.

Contractor. Badger Drlg.

Issued. 9-21-63

County Sherman
KANSAS



Elevation. 3710' RB

CASINO:

8" 265'

Production. Dry

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

TOPS: SCOUT

Blaine	2895
Anhydrite	3095
Howard	4117
Topeka	4142
Heebner	4301
Toronto	4328
Lansing	4350
Base Kansas City	4707
Marmaton	4719
Cherokee	4852
Mississippi	5179
Total Depth	5280

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

06-22-1970