


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County. Sec. 2 Twp. 10S Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C S/2, S/2 NE
Lease Owner Thornton E. Anderson
Lease Name FINNESEY Well No. 1
Office Address 1515 Arapahoe, Suite 1055, Denver, CO
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 10-07 19 80
Application for plugging filed 10-07 19 80
Application for plugging approved 10-07 19 80
Plugging commenced 10-07 19 80
Plugging completed 10-07 19 80
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas available
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dwayne Rankin
Producing formation Depth to top Bottom Total Depth of Well 3520'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 3520'

Set 1st plug @ 660' with 60 sx.
2nd plug @ 300' with 30 sx.
3rd plug @ 40' solid bridge with 10 sx.
Rathole with 5 sx., 50/50 posmix, 4% gel.

Plug was down @ 10:00 p.m. 10-07-80.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1980

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.

My commission expires 08-18-84



CONTRACTOR'S WELL LOG

OPERATOR: Thornton E. Anderson
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: FINNISSEY #1
 LOCATION: C S/2 S/2 NE, Section 2-10S-15W
 Osborne County, Kansas
 SPUD DATE: 10-01-80
 COMPLETION DATE: 10-07-80

0	270	Sand & Shale
270	890	Shale & Sand
890	1094	Shale
1094	1126	Anhydrite
1126	1828	Shale
1828	2030	Lime & Shale
2030	2410	Shale
2410	2855	Lime & Shale
2855	3520	Lime
	3520	Rotary Total Depth

Spud hole @ 7:30 p.m. 10-01-80. Drilled 313' of a 12-1/4" hole. Ran 7 joints of 8-5/8" 24# casing (tally 303.62') Set @ 312'. Cemented with 200 sx. of common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 2:00 a.m. 10-02-80.

T.D. 3520'. Set 1st plug @ 660' with 60 sx., 2nd plug @ 300' with 30 sx., 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 4% gel. Plug was down @ 10:00 p.m. 10-07-80.

RECEIVED
 STATE CORPORATION COMMISSION

OCT 17 1980
 10-17-80
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the FINNISSEY #1, C S/2 S/2 NE, Section 2-10S-15W, Osborne County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 15th day of October, 1980.

Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public

