

15-141-01000-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

Osborne

County. Sec. 2 Twp. 10S Rge. 15W xx (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NE
Lease Owner D.R. Lauck Oil Company, Inc. & Whitestone Petroleum Corp.
Lease Name Finnesy Well No. 1
Office Address 301 S. Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 28, 19 63
Application for plugging filed September 28, 19 63
Application for plugging approved September 28, 19 63
Plugging commenced September 28, 19 63
Plugging completed September 28, 19 63
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	207'	8-5/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3770'-200' Mud
200'-196' Plug
196'-156' Cement, 25 sx, & 1/2 sack hulls.
156'- 40' Mud
40'- 36' Plug
36'- 6' Cement, 10 sx, & 1/2 sack hulls.
(Bottom of Cellar)

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1963
10-10-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Co.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John H. Knightley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John H. Knightley
301 S. Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1963

My commission expires March 12, 1967

Stella J. Lipp
Notary Public.



D. R. Lauck Oil Company, Inc.
and
Whitestone Petroleum Corporation

15-141-01000-00-00

Finnesy #1

SE SE NE Sec. 2-10S-15W
Osborne County, Kansas

Commenced: September 18, 1963
Completed: September 28, 1963

Casing Record: 207' 8-5/8" Cemented w/150 sacks Cement,
3 sacks Calcium Chloride.

Elevation: GL 1902; DF 1905; KB 1907.

Drillers Log

Tops

		Sample	Welex
Surface Clay	40		
Blue Shale	207	Anhydrite 1125+ 782	1114+ 793
Shale & Shells	415	Heebner 3061-1154	3056-1149
Shale	445	Toronto 3085-1178	3080-1173
Sand	465	Lansing-Kansas City 3113-1206	3111-1204
Shale & Shells	550	Base Kansas City 3381-1474	3374-1467
Sand	670	Conglomerate 3496-1589	
Hard Sand & Pyrite	675	Conglomerate Sand 3500-1593	3500-1593
Shale & Shells	780	Viola 3632-1725	3588-1681
Shale & Sand	830	Simpson 3616-1709	
Red Bed & Shale	910	Arbuckle 3740-1837	3657-1750
Shale, Red Bed & Sand	1125	Total Depth 3770-1863	3768-1861
Anhydrite	1155		
Shale & Shells	1810		
Lime & Shale	2070		
Shale & Lime	2200		
Lime & Shale	2240		
Sand	2252		
Shale & Shells	2265		
Shale & Lime	2660		
Shale & Shells	2670		
Broken Lime & Shale	2815		
Lime & Shale	2920		
Shale & Lime	2982		
Lime & Shale	3061		
Shale	3065		
Lime	3165		
Shale & Dolomite	3230		
Lime	3358		
Lime & Shale	3445		
Shale, Lime & Sand	3530		
Conglomerate, mostly chert	3595		
Shale, Lime & Chert	3650		
Shale & Lime	3715		
Simpson	3745		
Arbuckle	3770 RTD		

DST #1 (W) 3068-3095, open 30 min. w/weak blow
5 min. Recovered 5' mud.
ISIP 581#/30 min.
FSIP 70#/30 min.
IFP 31#
FFP 31#

DST #2, (W) 3134-3165, open 30 min. w/weak blow
5 min. Recovered 5' mud.
ISIP 1054#/30 min.
FSIP 150#/30 min.
IFP 39#
FFP 43#

RECEIVED
STATE CORPORATION COMMISSION

D&A

OCT 10 1963
10-10-63
CONSERVATION DIVISION
Wichita, Kansas