

State of Kansas



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
NOV 27 1961  
11-27-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. L. G. McClusky of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Cities Service Oil Co guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 553, Russell, Kansas 67665

Lease Name: Finnesy Well No. # 1

Location: 660' F N L--660' F W L Sec. 2 Twp. 10 Rge. 15 (E)(W) W

County: Osborne Total Depth 3485 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. L. G. McClusly was instructed to plug the well as follows:

8 5/8" 262' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 25 sax  
cement thru drill pipe. Mud to 250', set plug, & displaced 25 sax  
cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug with 1/2 sax  
hulls, & displaced 10 sax cement with Halliburton Cementing Company's  
cellar.  
pump truck, cementing to base of ~~cellar~~ cellar.

*Don L. Small*  
Conservation Division Agent