

State of Kansas



15-141-20093-00-00

FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

June 14, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Raymond Kaba of John O. Farmer, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Woodman-Iannitti Drilling Company

Complete Address: 1008 Douglas Bldg., 104 So. Broadway, Wichita, Kansas 67202

Lease Name: Hobrock Well No. 3

Location: SW NW SW Sec. 3 Twp. 10 Rge. 5 (E) (W)

County: Osborne Total Depth: 3625'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kaba was instructed to plug the well as follows:

8-5/8"-217'-circulated Elev. 2008 KB Anhydrite 1216'-1257' Circulate
hole and fill with mud. Pump 50 sacks cement through drill pipe at 830'.
Pump 30 sacks cement through drill pipe at 250'. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Cement rathole with 10 sacks cement. Cement used 50-50 Pozmix w/6% gel.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

[Signature]
Conservation Division Agent

JUN 22 1981
672-81

CONSERVATION DIVISION
Wichita, Kansas