

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3
Rev. 5-5-81

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981
10-13-81
CONSERVATION DIVISION
Wichita, Kansas

API Number 15- 141-20, 120-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name LAWBANGO DRILLING, INC.

Complete Address BOX 289 NATOMA, KANS. 67651

Lease Name FINNESY Well No. #1

Location NW-NE-NW Sec. 2 Twp. 10 Rge. 15 (East) (West)

County OSBORNE Total Depth 3200 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor LAWBANGO DRILLING.

Address BOX 289 NATOMA, KS. License No. _____

Operation Completed: Hour: 11:30 PM Day: 10 Month: OCT Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 166 FE SP. CUL. w/ 100 ST QUICK SET.
ORDERED 125 ST 50% PREMIX 4% GEL-2% CA-CL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM. WITH HEAVY MUD BETWEEN ALL PLUGS.
1 ST PLUG. @ 660 FE w/ 70 ST CNT.
2 ND PLUG. @ 240 FE w/ 40 ST CNT.
3 RD PLUG. -> SOLID BRIDGE @ 40 FE TO w/ 10 ST CNT.
5 ST IN RAT HOLE.

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Mason Schmidt
Conservation Division Agent

DATE 11-23-81

INV. NO. 8393-W