

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,093-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Woodman-Iannitti Drilling Company

Complete Address 1008 Douglas Bldg., 104 So. Broadway, Wichita, Ks 67202

Lease Name Hobrock Well No. 3

Location SW NW SW Sec. 3 Twp. 10 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3625'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor John O. Farmer, Inc. and Sun Oil Well Cementing Co.

Address 370 W. Wichita, Russell, Kansas License No. _____

Operation Completed: Hour: 12:15 PM Day: 14 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part _____ None _____

The above well was plugged as follows: 8-5/8"-241-175 Sacks common 2% gel 3% cc
Elev. 2008 KB Anhydrite 1216-57'

Hole circulated and filled with mud. 50 sacks cement pumped through
drill pipe at 830'. 30 sacks cement pumped through drill pipe at 250''

Hole filled with mud to 40'. Plug and $\frac{1}{2}$ sack hulls pushed to 40' and
hole cemented to base of cellar with 10 sacks cement. Rathole cemented
with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1981
6-22-81
CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated, Wichita, Kansas

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 7-27-81

INV. NO. 6073-W