

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 167-19229-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 10/18/1962

Well Operator: Robinowitz Oil Company KCC License #: 6883
(Owner / Company Name) (Operator's)

Address: 4200 E Skelly Drive, Suite 620 City: Tulsa

State: Oklahoma Zip Code: 74135-3210 Contact Phone: (918) 481 - 7130

Lease: Davidson Well #: 218 Sec. 32 Twp. 15 S. R. 11 East West

SE - NE - SE Spot Location / QQQQ County: Russell

*KCC Wichita
1650
330*

1650 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 286' Cemented with: 175 Sacks

Production Casing Size: 5 1/2" Set at: 3268' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Arbuckle 3268' to 3274' Open Hole

Elevation: 1818' (G.L. / K.B.) T.D.: 3274' PBTD: None Anhydrite Depth: 667'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): per KCC Specifications

RECEIVED

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

SEP 25 2006

If not explain why? _____

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Don Degenhardt

Phone: (620) 587 - 3936

Address: 1885 NE 100 Avenue City / State: Clafin, KS

Plugging Contractor: Mike's Testing & Salvage KCC License #: 31529
(Company Name) (Contractor's)

Address: PO Box 467, Chase KS 67524-0209 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/21/06 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SHOLOM DRILLING COMPANY, INC.
P. O. Box 7027
Tulsa, Oklahoma

NOV 1 1962

COMPANY: Robinowitz Oil Company & Petroleum Operating Company
FARM: Davidson #1-B
LOCATION: SE NE SE Sec. 32 T15S R11W - Russell County, Kansas
ROTARY DRILLING CONTRACTOR: Sholom Drilling Company, Inc.

COMMENCED: 10-18-62
COMPLETED: 10-26-62
I. P.:

Elevation: 1818' K.B.
Rotary TD: 3274'

Casing Record:
8-5/8" @ 286' w/175 sax
5-1/2" (used) @ 3268' w/100 sax

L O G

0 - 20 Clay
20 - 65 Post Rock
65 - 160 Shale
160 - 190 Sand
190 - 240 Shale & Clay
240 - 267 Sand, Shale, & Clay
267 - 286 Plug & Cement
286 - 332 Shale & Sand
332 - 340 Hard Sand & Pyrite
340 - 370 Sand
370 - 380 Sand & Shale
380 - 396 Hard Sand & Pyrite
396 - 410 Shale & Sand
410 - 465 Pyrite & Shale
465 - 667 Red Bed
667 - 697 Anhydrite
697 - 1310 Shale & Shells
1310 - 2580 Lime & Shale
2580 - 2890 Lime
2890 - 2957 Shale & Lime
2957 - 3235 Lime
3235 - 3263 Lime & Shale
3263 - 3266 Shale
3266 - 3274 Arbuckle

DST #1 2856-90
Rec. 570' GCWM

DST #2 3268-74
Rec. 1550' oil

Anhydrite 667-697 (dr)
Topeka 2607'
Heebner 2849'
Toronto 2871'
Douglas 2883'
Lansing 2943'
Base K.C. 3191'
Conglomerate 3238'
Reworked Simpson 3247'
Arbuckle 3266'

RECEIVED
SEP 25 2008
KCC WICHITA

STATE OF OKLAHOMA)
COUNTY OF TULSA) ss.

I, Joseph Teichman, President of Sholom Drilling Company, Inc. a corporation of the State of Oklahoma, domesticated in the State of Kansas, being first duly sworn under oath, says: That I have knowledge of the facts, statements and matters herein contained of the above described well as filed and that the same are true and correct.


Joseph Teichman

Subscribed and sworn to before me this 30th day of October, 1962.


Notary Public

My commission expires: 3-17-64

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Robinowitz Oil Company
4200 E Skelly Dr Ste 620
Tulsa, OK 74135-3210

October 31, 2006

Re: DAVIDSON #1B
API 15-167-19229-00-00
SENESE 32-15S-11W, 1650 FSL 330 FEL
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



Barry Metz
Deputy Director