

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: R.P. Nixon Oper., Inc.  
Address: 207 West 12th Street Hays, KS 67601  
Phone: (785) 628-3834 Operator License #: 5252  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10.13.06 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L/KC Depth to Top: 3495' Bottom: 3740' T.D. \_\_\_\_\_  
Arbuckle Depth to Top: 3815' Bottom: 3819' T.D. 3819'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-23,441 - 00 - 00  
Lease Name: Meier  
Well Number: 7  
Spot Location (QQQQ): C - SE - NW - SW  
1650 Feet from  North /  South Section Line  
4290 Feet from  East /  West Section Line  
Sec. 17 Twp. 14 S. R. 19  East  West  
County: Ellis  
Date Well Completed: 5.18.83  
Plugging Commenced: 10.20.06  
Plugging Completed: 10.20.06

KCC PICT  
10/30/06  
Per  
CP 2/3  
CP SD  
Pags

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200'	none
				4 1/2"	3818.5'	none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf-Tech perforated casing at 2100', 1500' & 750' with 2 spf. Allied Cementing tied on to casing and pumped 215 sx of 60/40 Pozmix, 10% gel, 1/4# Flo-seal. Maximum pressure 600#, ISIP 500#. KCC man Roger Moses witnessed the job. Job complete at 1:00 pm.

Name of Plugging Contractor: R.P. Nixon Oper., Inc. License #: 5252  
Address: 207 West 12th Street Hays, KS 67601  
Name of Party Responsible for Plugging Fees: R.P. Nixon Oper., Inc.  
State of Kansas County, Ellis, ss.  
Dan A. Nixon

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) 207 West 12th Street Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 25th day of October, 20 06  
\_\_\_\_\_  
Notary Public My Commission Expires: 3-12-2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 27 2006  
KCC WICHITA