

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation  
Address: 8080 E. CENTRAL SUITE 300 WICHITA, KS 67206  
Phone: (316) 636-2737 Operator License #: 5003  
Type of Well: GAS Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 8-16-2006 (Date)  
by: STEVE DURRANT (KCC District Agent's Name)  
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No  
Producing Formation(s): List All (If needed attach another sheet)  
CHESTER Depth to Top: 5676 Bottom: 5832' T.D. 5832'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 21250 15-025-21,550-00-00  
Lease Name: FRAME GAS UNIT  
Well Number: # 2-15  
Spot Location (QQQQ): SW - SW - NW - \_\_\_\_\_  
2310 Feet from ☒ North / ☐ South Section Line  
330 Feet from ☐ East / ☒ West Section Line  
Sec. 15 Twp. 34 S. R. 25 ☐ East ☒ West  
County: CLARK  
Date Well Completed: 7-25-2003  
Plugging Commenced: 10-17-06  
Plugging Completed: 10-19-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	806'	0
				4 1/2"	5832'	4250'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SAND AT 5626', BAILED 4 SXS CEMENT WITH BAILER, SET FLOOR, PULLED SLIPS, CUT SURFACE OFF 4' BELOW GROUND. HAD 28" STRETCH  
RIPPED CASING AT 4420', WORKED PIPE, RIPPED CASING AT 4250', WORKED PIPE FREE, PULLED CASING UP  
TO 840', PUMPED 15 GEL, 50 SXS CEMENT AT 840', PULLED TO 420', PUMPED 50 SXS, PULLED TO 40', CIRCULATED WITH 15 SXS,  
PULLED JOINT, SURFACE STAYED FULL, EMPTIED PIT, BACKFILLED CELLAR AND PIT.

Name of Plugging Contractor: QUALITY WELL SERVICE License #: 31925  
Address: 401 W. MAIN LYONS, KANSAS 67554

Name of Party Responsible for Plugging Fees: McCOY PETROLEUM CORPORATION  
State of KANSAS County, SEDGWICK, ss.

SCOTT HAMPEL, VICE PRESIDENT-PRODUCTION (Employee of Operator) or (Operator) on above-described well, being first duly  
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the  
same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E. CENTRAL - SUITE 300 WICHITA, KS 67206

SUBSCRIBED and SWORN TO before me this 26th day of OCTOBER, 20 06

My Commission Expires: 2-07-2010



Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 30 2006  
KCC WICHITA