

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Marlin Oil Corporation
Address: P.O. Box 14630 Oklahoma City, OK 73113
Phone: (405) 478-1900 Operator License #: 9228
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/30/2005 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4682' Bottom: 4704' T.D. 4816'
Lansing - KC Depth to Top: 4228' Bottom: 4331' T.D. 4650'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 047-20672 - 00 - 00
Lease Name: Belcher
Well Number: # 1
Spot Location (QQQQ): NE - SW - NW -
1650 Feet from North / South Section Line
330-990 Feet from East / West Section Line
Sec. 16 Twp. 26 S. R. 18 East West
County: Edwards
Date Well Completed: 8/12/1980
Plugging Commenced: 10/05/2006
Plugging Completed: 10/06/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	<u>1768'</u>	8 5/8"	<u>1768' 372'</u>	None
		Surface <u>PROD</u>	<u>4849'</u>	4 1/2"	<u>4849'</u>	<u>2165'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

POH w/ tbg, Load csg w/ mud & set 4 1/2" CIBP @ 4180' & cap w/ 2 sks cement. Cut & pull 4 1/2" csg from 2165'. TIH w/ tbg @ 1280'

Mix & spot 50 sks Class "A" cement up to 1115'. Pull up hole @ 422' & spot 50 sks cement up to 260'. POH w/ tbg

Top out 40' to surface w/ 12 sks cement. Well bore circulated on each cement plug & stayed full. Dig out & cut off 4' below ground level

and weld ID plate. Dig up rig anchors, backfill & smooth up.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: Marlin Oil Corporation

State of Oklahoma County, Oklahoma, ss.

W. R. Lynn (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY SEAL
MARLA PARKER
Oklahoma County (Signature)
Notary Public in and for
State of Oklahoma (Address)
03002956

[Signature]
P. O. Box 14630 Oklahoma City, OK 73113

My Commission EXPIRES and SWORN TO before me this 30 day of October, 2006

[Signature] My Commission Expires: _____
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 01 2006
KCC WICHITA