

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Marlin Oil Corporation
Address: P.O. Box 14630 Oklahoma City, OK 73113
Phone: (405) 478-1900 Operator License #: 9228
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/30/2005 (Date)
by: Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 4707' Bottom: 4711' T.D. 4790'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-069-20066-00-01
Lease Name: Davidson
Well Number: # 1
Spot Location (QQQQ): NE - SE - _____ - _____
1980 Feet from ☐ North / ☒ South Section Line
660 Feet from ☒ East / ☐ West Section Line
Sec. 16 Twp. 25 S. R. 29 ☐ East ☒ West
County: Gray
Date Well Completed: 1/05/1990
Plugging Commenced: 10/11/2006
Plugging Completed: 10/12/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	409'	8 5/8"	409'	None
		Surface	4805'	5 1/2"	4805'	646'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tbg stuck in well, 12/7/2004 Tbg cut off @ 4649', 4395', 3940' & 3000'. Top of fish @ 3000'. TIH w/ tbg @ top of fish, mix & spot 50 sks

Class "A" cement w/ 1 sk cottenseed hulls & circ hole w/ mud. Weld on pull sub, Cut csg @ 1024', could not pull csg, cut again @ 646', POH w/ csg. TIH w/ tbg @ 1850' & spot 50 sks cement, pull up hole @ 1030' & spot 100 sks cement, did not circ to surface.

WOC Tag TOC @ 504' w/ tbg. Pull up to 459' & spot 50 sks cement. Well circulated. POH w/ tbg & top out 40' to surface w/ 12 sks cement.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: Marlin Oil Corporation

State of Oklahoma County, Oklahoma, ss.

W. R. Lynn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



Carla Parker
Notary Public in and for
State of Oklahoma
03002956

P. O. Box 14630 Oklahoma City, OK 73113

My Commission Expires 04-26-2007 I TO before me this 30 day of October, 20 06

Carla Parker
Notary Public

My Commission Expires: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

NOV 01 2006

KCC WICHITA