

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Osborne County. Sec. 28 Twp. 10 Rge. 14 (E) W(W)

Location as "NE/CNW/SW" or footage from lines SE NW NE

Lease Owner Duke & Wood Drilling Company

Lease Name Harrell Well No. 1

Office Address Box 194, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed July 5, 1952

Application for plugging filed July 5, 1952

Application for plugging approved July 5, 1952

Plugging commenced July 5, 1952

Plugging completed July 5, 1952

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3654 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	147'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 147 ft., set bottom plug, dumped 20 sacks of cement on plug. Filled with heavy mud to 40 ft., set top plug, dumped 10 sacks of cement on top plug, filled to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shelley-Miller Drilling, Inc.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1952

My commission expires April 29, 1953.

Dean Cooley Notary Public

24-2675-S 2-52-20M

PLUGGING
FILE SEC 28 T 10 R 14
BOOK PAGE 28 LINE 43

JUL 30 1952
7-30-52
CONSERVATION DIVISION
Wichita, Kansas

COMPANY: Duke & Wood Drilling Company
 Box 194, Great Bend, Kansas
 Rotary Drilling Comms: 6-21-52
 Rotary Drilling Comp: 7-5-52

LOCATION: SE NW NE Sec. 28-10-14 Osborn County,
 Kansas, Harrell #1

CONTRACTOR: Shelley-Miller Drilling, Inc.
 205 Miller Building, Wichita, Kansas

CASING RECORD: 8 5/8" #24 Smls. Casing, set at 147' cemented with
 100 sacks cement

LOG

(Figures indicate bottom formation measurements from top rotary bushing)

Surface Clay	35
Sticky Shale	60
Shale and shells	250
Shale	370
Sand and Shale	515
Shells and Shale	645
Shale and Shells	975
Red Bed	1027
Anhydrite	1066
Shale and Shells	1585
Lime	1755
Lime, Shale and Shells	1880
Lime	2105
Lime and Shale	2260
Shale and Shells	2310
Lime and Shale	2500
Shale and Shells	2595
Lime and Shale	2685
Shale and Shells	2780
Lime	3003
Lime and Shale	3135
Lime	3580
Conglomerate	3654

Rotary T. D.

The undersigned, Richard A. Shelley, President of Shelley-Miller Drilling, Inc. hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING, INC.

By Richard A. Shelley
 President

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss:

BE IT REMEMBERED that on this 9th day of July, 1952, before me, the undersigned, a Notary Public, duly commissioned, in and for the county and state aforesaid, came Richard A. Shelley, President, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling, Inc., as President of said company, and he duly acknowledged the execution of the same for himself and for said Company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

[Signature]
 Notary Public

My commission expires:

March 19, 1953

PLUGGING
 WILE SEC 28 T 10 R 14C
 JUL 28 1953

STATE CORPORATION
 JUL 30 1952
 CONSERVATION DIVISION
 WICHITA, KANSAS