

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Osborne County, Sec. 15 Twp. 10 Rge. 14 West (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NW

Lease Owner Edwin B. Cox and Edwin L. Cox

Lease Name Meyer Well No. 1

Office Address Magnolia Building, Dallas, Texas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 9 19 52

Application for plugging filed September 9 19 52

Application for plugging approved September 9 19 52

Plugging commenced September 9 19 52

Plugging completed September 9 19 52

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3910 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	153'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 150 ft. from bottom. Plug down at 150 ft. and cemented with 15 sks. cement with 1 sk. hulls on top. Hole filled with heavy rotary mud to 35 ft. Plug set at 35 ft. and cemented with 10 sks. cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1952
9-13-52
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hilton Drilling Company, Inc.

Address P. O. Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. HILTON DRILLING COMPANY, INC.

(Signature) Henry Peacock Secretary

2421 Tenth, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of September, 19 52

Margaret Whitmore Notary Public

My commission expires April 4, 1952

23-8890-s 6-51-20M

PLUGGING
FILE SEC 15 T 10 R 1 (C)
BOOK PAGE 43 LINE 23

DRILLER'S LOG

Company: Edwin B. Cox and Edwin L. Cox Location: NW NW NW 15-10-14
 Contractor: Hilton Drilling Company, Inc. Osborne County, Kansas
 Farm Name: Meyer No. 1 Elevation: 2021 DF
 Commenced: 8-22-52
 Completed: 9-9-52

Casing Used: 153' 8 5/8 with 150 sacks

Rock, Shale, and Chat	40
Rock and Clay	54
Cleachy	60
Rock and Cleachy	150
Shale and Shells	485
Shale, Shells, and Sand	660
Shale, Shells, and Red Bed	730
Sand	745
Hard Sand and Iron	750
Shale, Shells, and Sand	975
Shale, Shells, and Red Bed	1145
Anhydrite	1180
Shale, Shells, and Red Bed, Gypsum and Iron	1385
Shells and Shale	1685
Lime and Shale	1880
Lime Broken	1995
Lime	2110
Lime and Shale	2205
Lime and Shale	2205
Lime	2270
Lime and Shale	2948
Lime	3105
Shale and Lime	3218
Lime	3549
Lime and Shale	3614
Conglomerate	3658
Conglomerate, Chert, and Lime	3698
Shale, Lime, and Chert	3736
Conglomerate	3826
Conglomerate and Lime	3880
Lime	3910
Total Depth	3910

RECEIVED

STATE CORPORATIONS COMMISSION

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

SEP 12 1952
 9-12-52
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 15T10 R(40)
 BOOK PAGE 43 LINE 23

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

Subscribed and sworn to before me this 11th day of September, 1952.

Margaret Whitman
 Notary Public
 My commission expires 4-4-56.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary