

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Liberty Operations & Completions Inc

API Number: 15-163-01481-00-00

Address: 308 W Mill Plainville, KS 67663

Lease Name: Diehl

Phone: (785) 434-4686 Operator License #: 8925

Well Number: 2

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): SE - SW - NW -
2970 Feet from North / South Section Line

The plugging proposal was approved on: 10/15/06 (Date)

4290 Feet from East / West Section Line

by: Herb Dienes & Richard Williams KCC District Agent's Name

Sec. 5 Twp. 9 S. R. 17 East West

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Rooks

Producing Formation(s): List All (If needed attach another sheet)

Date Well Completed: 10/1955

Arbuckle & LKC Depth to Top: 3144 Bottom: 3423 T.D. 3423

Plugging Commenced: 10/15/06

Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Completed: 10/31/06

Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	<u>12 1/2</u>	surf	115'	8 5/8	32#	0
	<u>778</u>	115	3423	5 1/2	14#	0
Cement & Plugging material in hole.						
400 Bls. heavy rotary mud, 90 Bls. Polymer/470 SX cement. Pressure 300#						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Lost circulation in salt section. Pump in 190 sx to 1680' - wait 3 days

Spot 30 sx common 3%cc @ 1300' - wait overnight

Circulate 100 sx @ 1000' to surface, squeeze from surface 50 sx, squeeze annulus 50 sx all 60/40 poz. 10% gel

Name of Plugging Contractor: Allied Cementing License #: 8925

Address: Russell, KS


Name of Party Responsible for Plugging Fees: Roger Comeau

State of Kansas County, Rooks, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 308 W Mill, Plainville, KS 67663



SUBSCRIBED and SWORN TO before me this 31 day of October, 2006

Sandra Chard My Commission Expires: 9/15/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 02 2006
KCC WICHITA