

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21846-00-00
Spot: W2SWSE Sec/Twnshp/Rge: 20-10S-25W
660 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHAMBERGER Well #: 1
County: GRAHAM Total Vertical Depth: 4088 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S. BROADWAY, STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4089	0	w/150 sxs cmt
SURF	8.625	249	0	w/178 sxs cmt

\$132.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/2006 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DALE GRIFFIN Company: MID-CONTINENT ENERGY CORP. Phone: (316) 265-9501

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Multiple stage collar at 1247' w/400 sxs.
Perfs LKC 3966' - 4039'.
Dakota 976' - 1276'. Anhy 2176' - 2211'. Salt 2400' - 2600'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/23/2006 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 3011'.
Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 2250'. Allied rigged to tubing and pumped 50 sxs with 100# hulls mixed in to circulate cement to surface.
Pulled tubing. Allied rigged to 4 1/2" casing and pumped 20 sxs with 100# hulls mixed in.
Blew small hole in casing below head.
No shut in pressure. Rigged to 8 5/8" casing.
Max. P.S.I. 600#. S.I.P. 600#.

Perfs:

INVOICED
DATE 10/26/06
TEL. NO. 2007060743


Remarks: ALLIED CEMENTING COMPANY-TICKET #25374.

Plugged through: TBG

District: 04

MB

Signed _____



(TECHNICIAN)

OCT 23 2006

RECEIVED Form CP-2/3
OCT 26 2006
KCC WICHITA

MB

MID-CONTINENT ENERGY CORPORATION REPLACEMENT CARD 20-10-25W
 120 S. MARKET, #712 #1 SCHAMBERGER C W/2 SW SE
 WICHITA, KS 67202

CONTR B & B DRILLING, INC. CITY GRAHAM

GEOLOGICAL FIELD WC(GURK SE DISC)

+	+	+
+	+	+
+	+	+

ELV 2526 KB SPD 9/3/83 CARD ISSUED 10/27/83 IP P 80 BOPD, NW

2518 GL LKC 3966-4039 OA
 API 15-065-21,845

LOG	Tops	Depth/Datum	
ANH	2176 +	350	8 5/8 " 249/178SX, 4 1/2 " 2089/150SX, MULTIPLE STAGE COL-LAR AT 1247/400SX DST (1) 3855-90 (LKC 35&50'ZNS) / 30-30-30-45, SS/ 3", 1458' GIP, REC 930' CL GSY OIL (32° GR AT 90°), 90' HOOCM, SIP 1116-1102#, FP 79-227 / 268-381# DST (2) 3990-28 (LKC 70&90' ZNS) / 30-30-60-60, FB, 20' GIP REC 20' CL GSY OIL (35° GR AT 84°), 70' HC&GCM (30% OIL), SIP 1059-1069#, FP 29-45 / 45-57#, BHT 110° DST (3) 3945-85 (LKC 140' ZN) / 30-30-30-30, VWP & DIED 15", REC 30' M, W/ FEW SPTS OIL, SIP 972-972#, FP 29-28 8-8# BHT 110° DST (4) 3984-4027 (LKC 160&190' ZNS) / 30-30-30-45, SS OFF BTM 5', 1490' GIP, REC 406' CL GSY OIL (31° GR AT 78°), 30' G&MCO SIP 1283-1260#, FP 57-125 / 127-182#, BHT 112° DST (5) 4024-48 (LKC 200' ZN) / 30-30-30-45, SS OFF BTM 3" 306' GIP, REC 870' CL GSY OIL (38° GR AT 76°), 60' HOOCM, SIP 1036-1029#, FP 64-127 / 216-219# BHT 113° DST (6) 4047-465 (LKC 230' ZN) / 50-30-30-30, VWP & DIED 15" REC 30' M, W/ FEW SPTS OIL, SIP 972-972#, FP 29-28 8-8# BHT 110°
B/ ANH	2211 +	315	
TOP	3579	1053	
HEEB	3793	1267	
TOR	3815	1289	
LANS	3832	1306	
BKC	4058	1532	
PBTD	4085	1559	
RTD	4090	1564	
LTD	4088	1562	

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

1310
 1310
 1310