

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03466-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 26-11S-17W
990 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HALL B Well #: 19
County: ELLIS Total Vertical Depth: 3512 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3512	0	150 SX CMT.
SURF	8.625	1070	0	500 SX CMT.

114-14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2006 12:30 PM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 600# hulls.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2006 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 550' - 1080' - 1850'.
TIH with tubing to 3400' - mixed and pumped 120 sxs cement with 600# hulls.
Pulled up to 1800' - circulated up 5 1/2" with 125 sxs cement.
POOH. Swaged onto 5 1/2" - circulated cement up 8 5/8".
Shut in and continued to pump to pressure with 155 sxs.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3451	3461		
3436	3444		
3415	3431		

INVOICED
DATE 10/26/06
AMOUNT 200,706.00


Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

170

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

OCT 26 2006

KCC WICHITA

OCT 23 2006



3210

7
7

CITIES SERVICE OIL CO

#B-19 HALL

26-11-17W

N2 SW SW

Contr.

ELLIS County

E 1956

Comm. 9-3-46

Comp. 9-20-46

IP

D & A

Tops	Depth	Datum
ANH	1145	
ARB	3419	
TD	3512	

Casing

8" 1070

5" 3512

Perf 5 1/4 / 3 1/4 0-61: A/1000

Pmp 67 BO + 4% BS & W/24 hr

71 / 3 1/4 15-31: A/1000, wtr

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS