

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20444-00-00
Spot: N2N2N2 Sec/Twnshp/Rge: 22-10S-16W
4950 feet from S Section Line, 2645 feet from E Section Line
Lease Name: CONGER A Well #: 2
County: ROOKS Total Vertical Depth: 832 feet

Operator License No.: 8735
Op Name: CRAWFORD, STEPHEN G. DBA S & M O
Address: 1725 250TH AVE.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	828	0	w/100 sxs common-2% gel
SURF	7	54	0	w20 sxs common

\$ 35.00

Well Type: SWD UIC Docket No: D16579.0 Date/Time to Plug: 10/24/2006 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE CRAWFORD Company: S&M OIL Phone: (785) 650-4003

Proposed Plugging Method: Ordered 75 sxs 60/40 pozmix - 10% gel - 300# hulls.
Junk in the hole - left bad tubing and packer in the hole.
Dug out well head and found cement to surface in 4 1/2" x 7" annulus.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2006 10:00 AM KCC Agent: MARVIN MILLS / HERB DEINES

Actual Plugging Report:

Pumped 60 sxs 60/40 pozmix - 10% gel down the tubing set at 748' w/200# hulls.
S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
751	793		w/22 shots

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Marvin Mills
(TECHNICIAN)

OCT 25 2006

RECEIVED
OCT 27 2006
KCC WICHITA