

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00062-00-01

Spot: NENENW

Sec/Twnshp/Rge: 22-10S-16W

4950 feet from S Section Line,

2970 feet from E Section Line

Lease Name: CONGER A OWWO

Well #: 1

County: ROOKS

Total Vertical Depth: 3689 feet

Operator License No.: 8735

Op Name: CRAWFORD, STEPHEN G. DBA S & M O

Address: 1725 250TH AVE.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3640	0	
SURF	8.625	245	0	

\$ 119.89

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/24/2006 10:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: STEVE CRAWFORD

Company: S&M OIL

Phone: (785) 650-4003

Proposed
Plugging
Method:

Ordered 185 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/24/2006 11:30 AM

KCC Agent: MARVIN MILLS / HERB DEINES

Actual Plugging Report:

Perfs:

Pumped 180 sxs 60/40 pozmix - 10% gel with 700# hulls.
Max. P.S.I. 500#. S.I.P. 425#.
Tied onto backside and found it full of cement - pressured right up.

INVOICED
DATE 10/30/06
REF. NO. 2007060748

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

[Signature]

OCT 25 2006

OCT 27 2006

KCC WICHITA

R. W. RINE DRILLING CO.

#1 CONGER 'A'

22-10-16W

NE NE NW

CONTR UNKNOWN

CTY ROOKS

GEOL

FIELD NATOMA

E 2054 RB CM ?

CARD

ISSUED

11/29/62 IP

11 BOPD & 60% WTR,

SNDY CONG 3554-56

Date of Appraisal 6-5-72

API NOT ASSIGNED

SMP	TOPS	DEPTH	DATUM
ANH		1240	+ 814
FT RI		2030	+ 24
TOP		2930	- 876
LANS		3208	-1154
BKC		3510	-1456
SNDY CONG		3551	-1497
CHTY CONG		3557	-1503
REW ARB		3623	-1569
ARB		3639	-1585
TD		3689	-1635

SURF CSG UNKNOWN

OLD INFO: OPERATOR WAS CITIES SERV

#1 CONGER, COMPLETED AS D&A 2/25/42

NEW INFO:

MICT - CO, 3640, 4" 3640, PF 4/3359-60, 12/3562-65, FU 1050' WTR, ACID 50' NO TST, SQZ, 75 SX, PF 4/3568-69, BAIL WTR/TR 0, PB 3566, PF 8/3554-56, BAIL WTR, TR/0, AC 250, SWB LD, LOTS OF WTR, SWB 16 BFPH, 60-65% WTR

CORRECTION: 4/21/79

LANS WAS 3280-1226

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS