

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20416-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 8-21S-11E
694 feet from N Section Line, 476 feet from W Section Line
Lease Name: REES Well #: 8-11
County: LYON Total Vertical Depth: 2334 feet

Operator License No.: 4476
Op Name: WHITING OIL AND GAS CORPORATIO
Address: 1700 BROADWAY #2300 TWO UNITED
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2333	0	155 SX CMT
SURF	8.625	205	0	99 SX CMT

\$ 75.86

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/09/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: DARRELL MAHLOCK Company: _____ Phone: (580) 661-3536

Proposed Plugging Method: THE BOTTOM PLUG IS TO BE SET 25' FROM PBTD IF NOT PERFORATED. MIDDLE PLUG IS TO BE SET 25' ABOVE DOUGLAS. CIRCULATE TO SURFACE FROM 200' AND PUT GEL SPACERS BETWEEN CEMENT PLUGS. IF PERFORATIONS ARE PRESENT PLACE CEMENT 50' BELOW PERFS AND 50' ABOVE PERFS.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2006 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1999' pumped 35 sxs cement, pulled tubing out, shot casing @ 800' & 232', could not pull casing, ran tubing to 800' pumped 25 sxs cement, pulled tubing to 250' pumped 70 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DISTRICT #3

OCT 23 2006 MH

CHANUTE, KS

INVOICED
DATE 10/30/06
IN. NO. 2007060746

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern by SL
(TECHNICIAN)

RECEIVED
OCT 27 2006
KCC WICHITA

FED ID# 48-1214033
 MC ID # 156212
 Shop # 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Truck Services, Inc.
P.O. Box 782228
Wichita, KS 67278-2228

Cement and Acid
Service Ticket
T 1538

DATE 10-9-06

COUNTY Lyon CITY _____

CHARGE TO Whiting Oil & Gas Corp.

ADDRESS 1700 Broadway, Suite 2300 CITY Denver ST CO. ZIP 80290

LEASE & WELL NO. Rees 8-11 CONTRACTOR Hurricane Well Serv.

KIND OF JOB Plug To Abandon SEC. _____ TWP. _____ RNG. _____

DIR: TO LOC. W on 130th To Road H, S. 1 mile, west of Bridge, Through Farmers Place (Bean Field) OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
130	SKs. 60/40 Pozmix cement	600.00	
450	lbs. Gel 4%	963.30	
		81.00	
600	lbs. Gel Spacers between Plugs	108.00	

	BULK CHARGE		
m/c	BULK TRK. MILES 5.6 Tons > minimum charge	200.00	
20	PUMP TRK. MILES	55.00	
	PLUGS		
		Sub Total	2007.30
		SALES TAX	
		TOTAL	

T.D. PBTD 2291-

SIZE HOLE 7 7/8"

MAX. PRESS. _____

PLUG DEPTH _____

PLUG USED _____

CSG. SET AT _____ VOLUME _____

TBG SET AT _____ VOLUME _____

SIZE PIPE 5 1/2" - 205' of 8 5/8" S/P

PKER DEPTH _____

TIME FINISHED 2:00 p.m.

REMARKS: Safety Meeting: 10-6-06 > - Pumped 400# Gel Spacers, Spot 35 SKs Plug at 1999-
10-9-06 > Shot casing off at 232', Run 2 1/8" Tubing in hole to 800', Pumped Gel Spacer, Spot 25 SK Plug
Pull Tubing up to 250', Break circulation with water, Mixed 70 SKs Cement with Good Returns to Surface
Pull Tubing out of well - Jill Hole up with cement

EQUIPMENT USED

NAME Heath Watts UNIT NO. 185-

Brad Butler
 CEMENTER OR TREATER

NAME Don #91 UNIT NO. _____

Witnessed by Darrell
 OWNER'S REP.

RECEIVED
 OCT 27 2006
 KCC WICHITA