

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20413-00-00
Spot: NWSE Sec/Twnshp/Rge: 28-20S-12E
3301 feet from N Section Line, 3315 feet from W Section Line
Lease Name: SCHMIDT Well #: 28-33
County: LYON Total Vertical Depth: 2090 feet

Operator License No.: 4476
Op Name: WHITING OIL AND GAS CORPORATIO
Address: 1700 BROADWAY #2300 TWO UNITED
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2085	0	150 SX CMT
SURF	8.625	209	0	96 SX CMT

\$ 67.93

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/11/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: DARRELL MAHLOCK Company: _____ Phone: (580) 661-3536

Proposed Plugging Method: THE BOTTOM PLUG IS TO BE SET 25' FROM PBTD IF NOT PERFORATED. MIDDLE PLUG IS TO BE SET 25' ABOVE DOUGLAS. CIRCULATE TO SURFACE FROM 200' AND PUT GEL SPACERS BETWEEN CEMENT PLUGS. IF PERFORATIONS ARE PRESENT PLACE CEMENT 50' BELOW PERFS AND 50' ABOVE PERFS.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/12/2006 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1999', pumped 35 sxs cement, pulled tubing out, shot casing @ 243', ran tubing to 800' pumped 25 sxs cement, pulled tubing to 250' pumped 65 sxs cement to surface. Gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DISTRICT #3
OCT 23 2006 MH

INVOICED
DATE 10/30/06
WEL. NO. 200-70100-746

Remarks:

Plugged through: TBG

District: 03

Signed Miko Heffern
(TECHNICIAN)

RECEIVED
Form CP-2/3
OCT 27 2006
KCC WICHITA

FED ID# 48-1214033
 MC ID # 156212
 Shop # 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Truck Services, Inc.
P.O. Box 782228
Wichita, KS 67278-2228

Cement and Acid
Service Ticket
T 1542

DATE 10-12-06

COUNTY Lyon CITY _____

CHARGE TO Whiting Oil & Gas Corp.

ADDRESS 1700 Broadway, Suite 2300 CITY Denver ST CO. ZIP 80290

LEASE & WELL NO. Schmidt #28-33 CONTRACTOR Hurricane Well Serv.

KIND OF JOB Plug To Abandon SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. East on 90th To Rd R-5, South Yarmite, East into OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			600.00
125	SKs. 60/40 Pozmix cement		926.25
430	lbs. Gel 4%		77.40
600	lbs. Gel > Spacers between Plugs		108.00
	BULK CHARGE		
m/c	BULK TRK. MILES <u>Tons > minimum charge</u>		200.00
15	PUMP TRK. MILES		41.25
	PLUGS	Sub Total	1952.90
		SALES TAX	
		TOTAL	

T.D. PBTD 2044

CSG. SET AT _____ VOLUME _____

SIZE HOLE 7 7/8"

TBG SET AT _____ VOLUME _____

MAX. PRESS. _____

SIZE PIPE 5 1/2" - 208' of 8 5/8" S/P

PLUG DEPTH _____

PKER DEPTH _____

PLUG USED _____

TIME FINISHED 12:00p.m.

REMARKS: 10-11-06 > Rig up to Tubing set of 1999', Pumped 400# Gel, Spot 35 SKs. cement Plug
Pull Tubing out of well. 10-12-06 > Shot casing at 243', could not pull casing, Run Tubing in well to 800'
Rig up to Tubing, Pumped 200# Gel, Spot 25 SKs. cement, Pull Tubing up to 250', Rig up to Tubing
Mixed 65 SKs. cement - Good cement returns to surface - Pull Tubing out of well
Fill casing back up with cement - Job complete - Teardown

EQUIPMENT USED

NAME Heath Watts UNIT NO. 185

NAME Dan UNIT NO. #91

Brad Butler
 CEMENTER OR TREATER

witnessed by Darrell
 OWNER'S REP.

RECEIVED

OCT 27 2006

KCC WICHITA