

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-111-20414-00-00

Spot: SWNENWNW

Sec/Twnshp/Rge: 9-20S-12E

653 feet from N Section Line,

733 feet from W Section Line

Lease Name: FARR

Well #: 9-11

County: LYON

Total Vertical Depth: 2132 feet

Operator License No.: 4476

Op Name: WHITING OIL AND GAS CORPORATIO

Address: 1700 BROADWAY #2300 TWO UNITED  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2132	0	155 SX
SURF	8.625	203	0	76 SX
T1	2.875	2053	2053	

\$ 69.29

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/06/2006 8:00 AM

Plug Co. License No.: 32006

Plug Co. Name: HURRICANE WELL SERVICE, INC.

Proposal Rcvd. from: DARRELL MAHLOCK

Company:

Phone: (580) 661-3536

Proposed  
Plugging  
Method:

THE BOTTOM PLUG IS TO BE SET 25' FROM PBTD IF NOT PERFORATED. MIDDLE PLUG IS TO BE SET 25' ABOVE DOUGLAS. CIRCULATE TO SURFACE FROM 200' AND PUT GEL SPACERS BETWEEN CEMENT PLUGS. IF PERFORATIONS ARE PRESENT PLACE CEMENT 50' BELOW PERFS AND 50' ABOVE PERFS.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/06/2006 5:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1999' pump 35 sxs cement, shot casing @ 600' & 250', could not pull casing, ran tubing to 600', pumped 25 sxs cement, pulled tubing to 250' pumped 60 sxs cement to surface.

RECEIVED  
KCC DISTRICT #3

OCT 23 2006 MH

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1938	1945		
1920	1922		
1777	1779		
1753	1755		
1721	1723		
1707	1709		

INVOICED

DATE

10/30/06

2007060744

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern  
(TECHNICIAN)

RECEIVED  
Form CP-2/3

OCT 27 2006

KCC WICHITA

FED ID# 48-1214033  
 MC ID# 156212  
 Shop # 620 437-2661  
 Cellular # 620 437-7582  
 Office # 316 685-5908  
 Office Fax # 316-685-5926  
 Shop Address: 3613A Y Road  
 Madison, KS 66860

**Hurricane Truck Services, Inc.**  
**P.O. Box 782228**  
**Wichita, KS 67278-2228**

**Cement and Acid**  
**Service Ticket**  
**1537**

DATE 10-6-06

COUNTY Lyon CITY \_\_\_\_\_

CHARGE TO Whiting Oil & Gas Corp.

ADDRESS 1700 Broadway Suite 2300 CITY Denver ST CO. ZIP 80290

LEASE & WELL NO. FARR 911 CONTRACTOR Hurricane Well Serv.

KIND OF JOB Plug To Abandon SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR. TO LOC. Fracture 130<sup>3</sup> g/l 99 Hwy. To Road (4.5) South into OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			600.00
130	SKs 60/40 Pozmix cement		963.30
450	lbs Gel 4%		81.00
600	lbs Gel > Spacers Between Plugs		108.00
13	Mrs. Water Truck		975.00
	BULK CHARGE		
n/c	BULK TRK. MILES 5.6 Tons > minimum charge		200.00
15	PUMP TRK. MILES		41.25
	PLUGS		
		Sub Total	2968.55
		SALES TAX	
		TOTAL	

T.D. PBTD 2078

CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

SIZE HOLE 7 7/8

TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS. \_\_\_\_\_

SIZE PIPE 5 1/2" 205' of 8.5" SIP

PLUG DEPTH \_\_\_\_\_

PKER DEPTH \_\_\_\_\_

PLUG USED \_\_\_\_\_

TIME FINISHED 1:00 pm

REMARKS: Safety Meeting:

35 sk. Plug at 1999'  
25 sk. Plug at 1017'  
60 sk. Plug at 250' to Surface

Note: SpT Gel Spacers between Cement Plugs

**EQUIPMENT USED**

NAME Heath Watts UNIT NO. 185  
 \_\_\_\_\_  
 \_\_\_\_\_  
 CEMENTER OR TREATER

NAME Dan 91 Ronny 155  
 \_\_\_\_\_  
 \_\_\_\_\_  
 OWNER'S REP.

**RECEIVED**

OCT 27 2006

**KCC WICHITA**